## ND Asphalt Conference

### NDDOT Update



a second

Transportation

#### **NDDOT Construction Program**

(\$\$ Millions)





Transportation

# GRANT UPDATE

- \$55 million for US 85 four lane
- \$9.85 million RAISE Grant for Tribal Bike Paths
- Bidding the last US 52 Passing lane, an INFRA grant project
- Bidding Fort Yates Roundabout Tribal Safety project – RAISE Grant







NORTH Akota | Trans

Transportation

Be Legendary.

# HMA UPDATE

- 1,361,467 Tons of Asphalt bid in 2023
- Tons including RAP = 58%
- Binder Used
  - 13% 58S-28
  - 21% 58S-34
  - 59% 58H-34
  - 7% 58H-28, 58V-28, 58V-34



# DENSITY RESULTS

- 2023 Avg Mainline Density: 93.4
  - 2022 Avg 93.8
  - 2021 Avg 93.6
  - 2020 Avg 93.4
  - 2019 Avg 93.4
  - 2018 Avg 92.9
- 2023 Avg Joint Density: 92.1
  - 2022 Avg 92.3



Transportation

# 2023 HMA INCENTIVE \$

- Ride Incentive \$594,000
  - Avg MRI 39.3
- Mainline Density
  - Avg Pay Factor 101.3%





Transportation

### HMA SELECTION GUIDE

 Daily One-way ESAL's
 Superpave FAA Type

 < 100</td>
 FAA 42

 & Interstate shoulders
 FAA 42

 100 - 300
 FAA 43

 > 300
 FAA 45

 & Roundabouts
 FAA 45

- Superpave FAA Type
- Binder Grade

Performance Graded (PG) Asphalt Binder Selection Guide with MSCR

Daily One-way ESAL's	PG Binder Grade
< 100 & Interstate shoulders	PG 58S-28
100 – 200	PG 58S-28 with < 20% RAP PG 58S-34 with <u>&gt;</u> 20% RAP
200 - 1000	PG 58H-34
> 1000 & Roundabouts	PG 58V-34

 Daily One-way ESAL's are published each year by Planning/Asset Management Division and can be found in the District Highway Information book for each Hwy segment.

Superpave FAA Type



### PILOT PROJECTS COMPLETED 2023

- Superpave 5 Fargo Project
- High RAP Valley City Project
- Intelligent Compaction 10 projects
- Paver Mounted Thermal Profiler 10 Projects
- Percent Within Limits 5 Projects











# SUPERPAVE 5

- Target 5% air voids at mix design and compact to 95%
- Current Superpave method is 4% air voids and compact to 7% on the road.
- N<sub>design</sub> of 30 gyrations instead of 75
  - Increased binder content





# SUPERPAVE 5



- SP Changes for 2024
  - Air Voids single test 3.5 to 6.5, previously 3.0 to 7.0
  - Air Voids range 4.0 to 6.0, previously 3.5 to 6.0
  - Min. Density for 100% pay moved from 92% to 94%



## DENSITY PROFILING (DPS)



- Grand Forks and Fargo projects profiled in 2023
- Presentation at CAPRI



Transportation

### HIGH RAP

- 35% RAP content
- Ideal CT Avg: 46
- Hamburg: 6 mm @20,000

#### 2023 HMA Performance Testing Results

Project #: SS-2-036(013)062 PCN: 23465

Highway/Interstate: ND 36	Type: 1" Mill, 2" Overlay	FAA: 42	PIT COA: SN-1245		
Pit Name: Odenbach	PG Oil: 585-34	PG Brand: Cenovus (Husky)	RAP: 35%		
The Hamer Galenbach	1000001	ro branar centras (nasia)	10 11 100 //		

Production Data						
Description	Test #1	Test #2	Test # 3			
Sample Date	6/1/2023	6/8/2023	6/15/2023			
Average Bitumen Content	3.71%	3.70%	3.68%			
IA 1/2"	99.0	98.0	99.0			
IA No. 4	56.0	61.0	55.0			
IA No. 30	9.5	17.0	17.0			
IA No. 200	3.6	5.1	5.8			
IA Lightweight Pieces	2.4%	2.0%	1.2%			
IA FAA	43	43	43			
IA Flat & Elgonated	-	-	-			
IA Fractured Faces	95%	92%	96%			
IA Sand Equivalent	59	57	62			
IA Air Voids	3.1%	3.8%	2.8%			
IA Bulk SpG	2.378	2.369	2.399			
IA Max SpG	2.454	2.463	2.467			



Transportation



# PILOT PROJECTS 2024

- Superpave 5
- Intelligent Compaction
- Paver Mnt. Thermal Profiler
- Percent Within Limits
- Higher RAP %
- Machine Guidance Milling
- 1 project 13 projects 13 projects 4 projects 1 project 1 project



Be Legendary.

### PAVEMENT PRESERVATION - TEST SECTION PROJECT



- Double Chip Seal
- Cape Seal
- RAP Cape Seal
- Double Micro-surfacing
- RAP Double Micro
- Ultra Thin Bonded
- 4.75 mm HMA Thinlay
- 2-inch overlay (control)
- 3 miles each



- Section 1 Double Chip Seal (0.5")
  - o RP 47.21 to RP 50
  - Cost per Mile: \$193,749
- Section 2 Cape Seal (0.5")
  - o RP 50 to RP 53
  - o Cost per Mile: \$166,644
- Section 3 RAP Cape Seal (0.5")
  - o RP 53 to RP 56
  - o Cost per Mile: \$169,938
- Section 4 Double Micro-surfacing (0.5")
  - o RP 56 to RP 59
  - o Cost per Mile: \$160,670



**RAP** Cape Seal



**RAP Micro-surfacing** 

# TEST SECTIONS



- Section 5 RAP Double Micro-surfacing (0.5")
  - o RP 59 to RP 62
  - o Cost per Mile: \$163,785
- Section 6 Ultra-thin Bonded (0.75")
  - o RP 62 to RP 65
  - o Cost per Mile: \$403,968
- Section 7 HMA 4.75 mm (0.75")
  - o RP 65 to RP 68
  - Cost per Mile: \$261,836
- Section 8 FAA 43 2" Overlay (2" Control)
  - o RP 68 to RP 72.2
  - Cost per Mile: \$389,486



#### Ultra-thin Bonded



#### 4.75 mm Overlay

# TEST SECTIONS



### 9.5 MM SUPERPAVE

- University Drive 5 lane section in S Bismarck
- 1.25" thickness
- Finished MRI of 31
- Special Provision available to use





# E-TICKETING

- Successfully used on 15 projects during 2023
- Special provision that allows for e-tickets on all projects
- Acquired DOT Portal by HaulHub to pilot this year
- Plan full implementation of e-ticketing by 2026

					· · · · · ·				
							ж		<b>B</b> 11
間 74 13	tal Tickets		Bellywood II DE Torro	215.0	fing) IIII Tarea	Rejected 15.90 Tons	Ticke	ted	_
							O that	skalvered	
8.0	Developed of the	0	EDVT DISLOWING				Toble	Airentei	
D 94	rest All Report	•					ant meaning the	-	
-	Contractor Services	print he	rations				Rev Hoher data		
	Tichel		Bete	10	Constant (a)	Toppler	ittelen. Magginer	-	11
	14807		2021-08-12 10:09-86 #1	0.13	NRC Approprie Topolite	ARCONTERNO	The second secon	Pare 14	
	14621		2021-06-12 7-29-14 wh		ADC Approprie Souther	ASC Contractor	Taken and a		-
	14747		2021-08-12 x 38.29 am		ART Appropria Topolar	ABC Community	201 2012		12
	14148		2221-08-10 10.07-01 we	e - 1	ASC Appropriet Surpline	ARC Contractor	Pare	84,0	1
	14140		2021-00101-04521-01		NK Approprie Souther	ARC Continuing			- 77-
	same		3521-09-10-7.16.51 av		NE Apparts Saufre	ARC Germanor	And and a second s	-	
	14794		3821-08-16 1/34-00 em		ARC Approprie Samplier	AIC Contractor	Turnet by		
	10836		2021-08-05 12:08:03 (**		NRC Approprie Transfer	RBC Contraction	Nº A		
	95820		2023-08-05 5 at 28 an		IR: Approprie lamples	ARC Contraction	Ava		
	10809		2221-08-05 9-94-07 wh		AMC Auguregate Transfer	ARC Contraction	Part annual line		
	30800		2021-08-08 7-09-11 am		NC Agangele Supple	ARC Contraction	trains.	1000) - 0000 5/4	801
			3823-08-05 6 38 52 em		All Agengets Souther	ARC Contraction			



### HMA SPEC CHANGES 2024

- Requirements around Mix
   Controller and Mix Designer
- Superpave 5 tighter Air void and density requirements
- Stone Matrix Asphalt Voids in Coarse Aggregate test





Transportation

### FHWA CLIMATE CHALLENGE

- NDDOT applied for a Grant in 2022 and received \$240,000
  - Training Fall 2023
  - Proposal Development
  - Develop a Sustainable Pavements Evaluation Process





Transportation

### TPF-5(478) DEMO TO ADVANCE NEW PAVEMENT TECH

- Project Timeframe: 2023 to 2026
- Benchmark ND mixes in 2022 and 2023
- Total Proposed Cost: \$350,000
  - \$250,000 from Pooled Fund
  - \$100,000 research funds approved by RAC
- Build BMD test sections for field verification 2024 construction
- Develop BMD specifications and implement through pilot projects





### BMD Validation... What type of Project?



- Thermal Cracking a concern with an overlay
- Transverse Cracks reflect in year 1
- Picked a cement treated FDR with widening
- 4" HMA on 10" cement treated base



### BMD STAKEHOLDER TEAM

- Knife River Materials
- Mayo Construction
- Border States Paving
- Northern Improvement
- Sundre Sand & Gravel
- Terracon
- Aaron Swan Labs
- NDDOT
- DAPA
- NCAT
- FHWA





Transportation

# STAKEHOLDER MEETING TOPICS

- Contractors asked for 1500 to 2000 tons of production before changing the mix
- Keep the variables to a minimum
- Portable plants typically only have 1 main liquid asphalt tank
- Crushing extra material to account for mix design variations would cost \$\$



Transportation



Transportation

# 8 TEST SECTIONS

- Each section is 2 miles in length
- 2 binder types, 58S-28 & 58H-34
- Vary the AC Binder content by 0.5% from optimum, add RAP in 2 sections
- 5.5%, 6.0%, 6.5%, 4.5%+RAP
- Same Aggregate gradation thru-out



NORTH



# PROJECT DETAILS

- Project was bid in February 2024
- Construct in Summer 2024
- Project Cost: \$20 million



Transportation

1941 in Cogswell, ND

### IMPLEMENTING BALANCED MIX DESIGN

- Step 1 Benchmarking Current Mixes 2022 and 2023
- Step 2 Field Validation Project 2024 Construction
- Step 3 Shadow Projects 2025
- Step 4 Develop specifications/Pilot Projects 2026
- Full Implementation ??







Transportation

### HMA PERFORMANCE TESTING

- Hamburg wheel tracker
  - Identified an area in SW ND with an aggregate stripping issue
  - Added a liquid anti-strip by change order after testing









Transportation

# QUESTIONS?



Transportation